

# L-200<sub>PRO</sub>

*Prefabricated Chamber Kit*

*Starting at*  
**\$49,995**

## About The L200

The L200<sub>PRO</sub> chamber features four fans and a power vent for intake and exhaust. Measuring 16 ft. wide by 8 ft. high, this chamber is capable of drying 3,000 - 4,000 BF of 4/4 green oak in 4 to 5 weeks.

This package includes an L200<sub>PRO</sub> DH Unit, control, four circulating fans, a powered vent kit, and a prefabricated chamber.



## Whats Included:

- ☒ L200<sub>PRO</sub> Dehumidification Kiln
- ☒ Pro Kiln Control
- ☒ Circulating Fans
- ☒ Powered Vent(s)
- ☒ Kiln Chamber Kit



## Learn More:



12 Stevens Road  
Brewer, ME 04412



(800) 777-6953



kilnsales@nyle.com  
www.nyledrykilns.com

# Specifications

Number of Fans	4
Fan HP	1/3 HP
Chamber Dimensions	17' 11" W x 8' 6" D x 12' H
Load Space	16' W x 4' D x 8' H
Maximum Chamber Capacity	4,000 Board Feet
Power Requirements	240V Single Phase, 60 Hz, Dedicated 100A Required.
Shipping Weight	10,000 lbs.
Shipping Requirements	Fork extensions are recommended.
Build Time	4 - 5 Days

